

Vendor 10034

184-21/28

Board 4/4

3/29/2022

TO: Zane Schreder

PHONE: (530) 228-9733
 EMAIL: zane@zaneschreder.com

FROM: Jeff Dickey, Beynon Sports
 MOBILE: (559) 287-3071
 EMAIL: jdickey@beynonsports.com

14 0605 0 5813 0000 8110 400 0000 XP

Patterson HS - Track Surfacing Proposal

Beynon Sports is pleased to present this proposal to supply and install new synthetic track surfacing per plans, specifications, and all addendums.

SYNTHETIC TRACK SURFACING	
Description:	New Synthetic Track Surfacing
Scope:	Beynon Sports proposes to scrape existing runways, clean existing runway base and supply and install new synthetic track surfacing.
Size:	110 Total Square Yards
Product:	BSS 100WB
Color:	Red
Texture:	Spray
Thickness:	13mm
Warranty:	3 Years
Striping:	All associated NFHS standard striping
Cost:	<u>\$24,260.00</u>
Duration of Work:	4 Days (Track Surfacing Crew)



SYNTHETIC TRACK SURFACING	
Description:	New Synthetic Track Surfacing
Scope:	Beynon Sports proposes to supply and install new synthetic track surfacing.
Size:	110 Total Square Yards
Product:	BSS 300
Color:	Red
Texture:	Embedded
Thickness:	13mm
Warranty:	3 Years
Striping:	All associated NFHS standard striping
Cost:	<u>\$29,740.00</u>
Duration of Work:	5 Days (Track Surfacing Crew)

- Beynon Sports is a licensed contractor in the State of California # 883198 A, C-15, C-61 / D-12
- **Beynon Sports CMAS #: 4-12-78-0063A and GSA # GS-07F-9631S**

This quotation excludes any bond costs, design costs, base work or repair of base, union or labor law levies, site security, agency approval or associated fees, fencing, protection of sports surface after completion, supply and installation of any equipment, logos, multiple mobilizations or other unforeseen costs.

- Beynon Sports DIR Registration Number: 1000004698
 - Beynon Sports acknowledges all Prevailing Wages, Applicable Taxes, Per Diem and Travel Time
 - Cure time on new asphalt and concrete is 28 days prior to receiving new track surface
 - No concrete curing compounds or asphalt seal coats shall be utilized
 - All flat concrete work shall have a medium broom finish
 - We recommend a moisture barrier under all concrete flat work, and/or a moisture mitigation system be applied topically to all concrete on which the synthetic track surfacing is to be applied
 - While surfacing and striping are being done, water systems must be curtailed, shut off or controlled so that no water falls on the track or event area surfaces
 - Upon completion of our track surfacing and line striping installation, all construction debris, materials and equipment will be cleaned up prior to Beynon demobilizing and turning the track over to the site
-
- **Due to the uncertainty and volatility in raw materials supplies, material costs, and shipping delays, this proposal is valid for 30 days**

If you have any questions regarding this proposal, please do not hesitate to contact me at the above-mentioned number or email.

Best Regards,
Jeff Dickey
Beynon Sports
(559) 287-3071